EVALUATION REPORT OF UNION CORRUGATING COMPANY '29 GA. MASTERRIB PANEL' OVER WOOD SUPPORTS

FLORIDA BUILDING CODE 7TH EDITION (2020) FLORIDA PRODUCT APPROVAL FL 9557.4-R5 PANEL WALLS SIDING

Prepared For: Union Corrugating Company 701 S. King St. Fayetteville, NC 28301 Telephone: (910) 483-0479 Fax: (910) 483-1091

Prepared By: Bala Sockalingam, Ph.D., P.E. Florida Professional Engineer #62240 1216 N Lansing Ave., Suite C Tulsa, OK 74106 Telephone: (918) 492-5992 FAX: (866) 366-1543


This report consists of Evaluation Report (2 Pages including cover) Installation Details (1 Page) Load Span Table (1 Page)

> Report No. C2372-4 Date: 8.7.2020



FL 9557.4-R5
C2372-4
8.7.2020
Page 2 of 2

Manufacturer:	Union Corrugating Company
Product Name:	MasterRib Panel
Panel Description:	36" wide coverage with 3/4" high ribs at 9" o.c.
Materials:	Minimum 29 ga., 80 ksi steel. Galvanized coated steel (ASTM A653) or Galvalume coated steel (ASTM A792) or painted steel (ASTM A755) as per FBC 2020 Section 1405.2.
Support Description:	Nom. 2" x 2" (min) SPF, SYP or DF lumber (Must be designed by others)
Design Pressure: (Based on testing)	+45.35 and -36.2 psf at support spacing of 48" o.c. (at 3 span condition with $FS = 2.0$)
Panel Attachment:	#9-15 or #10-14 x 1.5" long wood screws with washers. Corrosion resistant as per FBC 2020 Section 1405.17.
At panel ends At intermediate	at 3.5"-5.5"-3.5" o.c. across panel width at 9" o.c. across panel width
Sidelap Attachment:	$\frac{1}{4}$ "-14 x 7/8" long SDS with washer at 24" o.c. Corrosion resistant as per FBC 2020 Section 1405.17.
Test Standards:	Panel assembly tested in accordance with ASTM E1592-01 'Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference'.
Test Equivalency:	The test procedures in ASTM E1592-01 comply with test procedures prescribed in ASTM E1592-05(2012).
Code Compliance:	The product described herein has demonstrated compliance with FBC 2020 Section 1404.5.
Product Limitations:	Design wind loads shall be determined for each project in accordance with FBC 2020 Section 1609 or ASCE 7-16 using allowable stress design. The maximum support spacing listed herein shall not be exceeded. The design pressure for reduced support spacing may be computed using rational analysis prepared by a Florida Professional Engineer or based on Union Corrugating load span table. This product is not approved for use in the High Velocity Hurricane Zone.
Supporting Documents:	ASTM E1592 Test Report ENCON Technology Inc. C1514-1 (Test #2 & 3), Reporting Date 9/8/07



UNION CORRUGATING COMPANY MasterRib Wall Panel

Loading Allowable Load (psf) Span Condition Support Spacing (ft) Type 1.50 1.75 2.00 2.25 2.50 2.75 3.00 3.50 4.00 Two Span Positive 106.4 91.2 79.8 70.9 63.9 58.0 53.2 45.6 36.3 29.0 Negative 84.9 72.8 63.7 56.6 51.0 46.3 42.5 36.4 103.7 90.7 72.6 60.5 51.8 45.4 Three Span Positive 120.9 80.6 66.0 96.5 82.7 72.4 64.4 57.9 52.7 48.3 41.4 36.2 Negative 99.8 77.6 58.2 49.9 42.4 Positive 116.4 87.3 69.8 63.5 Four or More 61.9 50.7 Negative 92.9 79.6 69.7 55.7 46.5 39.8 33.8 Spans

36" wide, 29 ga. (min) Steel Panel over Wood Supports

Notes:

1. Allowable load for each condition is the smallest load calculated based on fastener capacity, panel strength and and deflection limit of L/120. Allowable loads are calculated for minimum 29 ga. panel.

2. The wind load is taken as 0.7 times the "component and cladding" loads for the purpose of determining deflection limit.

3. The panel allowable properties are determined from full scale ASTM E1592 tests at 4' 0" span

4. The panel fasteners are #9-15 or #10-14 x 1.5" long wood screws with washers. Fastener spacing across panel width is 9.0" o.c. in the interior supports and 3.5"-5.5"-3.5" o.c. at panel ends.

5. Sidelap fasteners are 1/4"-14 x 7/8" long self drilling screws with washer at 24" o.c.

6. Wood supports are minimum 2" x 2" lumber. All supports must be designed to resist all loads imposed on the panel.

7. Minimum bearing width of support is 1.5".

8. The panels may span from bottom to top supports or side to side supports.

9. Panels must be installed as per Evaluation Report FL 9557.4 and Union current installation procedure.



1216 N Lansing Ave. Suite C Tulsa, OK 74106 918 492 5992 Bala Sockalingam, Ph.D., P.E. PE 62240