EVALUATION REPORT OF UNION CORRUGATING COMPANY 'NOM 0.04'' THICK ALUMINUM SL175 PANEL'

FLORIDA BUILDING CODE 7TH EDITION (2020) FLORIDA PRODUCT APPROVAL FL 32186.3-R1 ROOFING METAL ROOFING

Prepared For: Union Corrugating Company 701 S. King St. Fayetteville, NC 28301 Telephone: (910) 483-0479 Fax: (910) 483-1091

Prepared By: Bala Sockalingam, Ph.D., P.E. Florida Professional Engineer #62240 1216 N Lansing Ave., Suite C Tulsa, OK 74106 Telephone: (918) 492-5992 FAX: (866) 366-1543

This report consists of Evaluation Report (3 Pages including cover) Installation Details (1 Page) Load Span Table (1 Page)

> Report No. C2407-3 Date: 10.13.2020



	FL 32186.3-R1	
	C2407-3 10.13.2020	
	Page 2 of 3	
Manufacturer:	Union Corrugating Company	
Product Name:	SL175	
Panel Description:	Standing seam panel with max. 18" wide coverage, 1.75" high ribs and snap lock seam.	
Materials:	Nom. 0.04" thick (min.) 3105-H14 Alloy (ASTM B209) as per FBC 2020 Section 1507.4.3.	
Deck Description:	Min. 15/32" thick APA rated plywood or min. ³ / ₄ " thick wood plank (min SG of 0.42) for new and existing constructions. For HVHZ, min. 19/32" thick plywood for new constructions and min. 15/32" thick plywood for existing constructions. Designed by others and installed as per FBC 2020.	
Underlayment:	Minimum underlayment as per FBC 2020 Section 1507.4.5.1. For HVHZ, minimum underlayment as per FBC 2020 Section 1518.2, 1518.3 and 1518.4.	
Slope:	1/4:12 or greater in accordance with FBC 2020 Section 1507.4.2 For HVHZ, 2:12 or greater in accordance with FBC 2020 Section 1515.2.	
Design Uplift Pressure: (Factor of Safety = 2)	52.5 psf at clip spacing of 24" o.c. 78.5 psf at clip spacing of 8" o.c.	
Panel Attachment:	18 ga., 3.5" long SL175 clip with (2) #10-12 x 1" long pancake head wood screws per clip through underlayment into deck. Fastener shall be of sufficient length to penetrate through the deck a minimum of 1/4". Clips and fasteners are corrosion resistant as per FBC 2020 Section 1506.7 and 1507.4.4, respectively.	
Test Standards:	Roof assembly tested in accordance with TAS 125-03 'Standard Requirements for Metal Roofing Systems', TAS 100-95 'Test Procedure for Wind and Wind Driven Rain Resistance of Discontinuous Roof Systems' and TAS 110-00 'Testing Requirements for Physical Properties of Roof Membrane, Insulation, Coatings and Other Roofing	

Code Compliance: The product described herein has demonstrated compliance with FBC 2020 Section 1504.3, 1507.4, 1518.9 and 1523.6.5.2.4.

Components'.

Design wind loads shall be determined for each project in accordance **Product Limitations:** with FBC 2020 Section 1609, Section 1620 or ASCE 7-16 using allowable stress design. Maximum clip spacing listed herein shall not


FL 32186.3-R1 C2407-3 10.13.2020 Page 3 of 3

be exceeded. The design pressure for reduced clip spacing may be computed using rational analysis prepared by a Florida Professional Engineer or based on Union load span table. This evaluation report is applicable in High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2020 Section 1505 and current approved roofing materials directory or ASTM E108/UL790 report from an accredited laboratory for fire ratings of this product.

Supporting Documents: TAS 125 Test Report Farabaugh Engineering and Testing Inc. Project No. T116-20, Reporting Date 4/23/20

> TAS 100-95 Test Report Farabaugh Engineering & Testing, Inc. Report No. T234-20, Reporting Date 5/31/2020

TAS 110-00 Test Report on Valspar Fluropon coated metal panels PRI Asphalt Technologies Report No. VLS-004-02-01, Reporting Date 2/22/2013 Report No. VLS-005-02-01, Reporting Date 2/22/2013



UNION CORRUGATING COMPANY SL175 Panel Uplift Loads (Nom. 0.04'' Aluminum)

Description	Clip Spacing	Allowable Uplift
	Along Panel Length	Load
	(in)	(psf)
Max Coverage width: 18"	8	78.5
Seam: Snap Lock	10	75.3
SL175 clip	12	72.0
3.5" long, 18 ga. clip	14	68.8
	16	65.5
	18	62.3
Clip Fasteners:	20	59.0
(2) #10-12 x 1" long pancake	22	55.8
head screws	24	52.5

Notes:

1. The bold numbers indicate design loads calculated from test data with safety factor of 2.

2. Panels must be installed as per Evaluation Report FL 32186.3 and Union current installation procedure.



1216 N Lansing Ave., Suite C Tulsa, Ok 74106 918 492 5992 Bala Sockalingam, Ph.D., P.E. FL 62240